SHIMOGA DIVISION.

Notice dated 27th October 1930.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Shimoga Division, up to 26th November 1930, till 3 P.M., for constructing Public Works Department Subordinate Quarters at Somalapur in Channagiri Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1931.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees one hundred and fifty in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing Public Works Department Subordinate Quarters at Somalapur in Channagiri Taluk, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate of quantities for the construction of Public Works Department Subordinate Quarters at Somalapur in Channagiri Taluk :—

No.	Items of work	Per	Quantity
1	Earthwork excavation for foundation and filling in basement ...	C.yd.	39
2	Stone jelly concrete in mortar	C.ft.	82
3	Burnt brick in clay for foundation and basement ...	,,	1,313
4	Do for superstructure	,,	1,414
5	Flat arch work brick in mortar	,,	75
6	Burnt brick in mortar for top of walls for sides of doors and windows.	,,	421
7	Cuddapah slabs 1½" thick	S.ft.	71
8	Burnt stone slabs roughly dressed and fixed 5" to 6" thick ...	,,	31
9	Mud plastering including cowdung washing	Sqr.	21·83
10	Chunnam plastering	,,	15·83
11	Cement pointing to basement	,,	2·91
12	Honne wood windows with battened shutters in 4 halves with iron bars and fittings, etc., complete.	S.ft.	95
13	Honne wood doors with battened shutters iron clamps and fittings, etc., complete.	,,	108
14	Flooring with 3" jelly concrete in mortar and cement plastering and cutting tiles, etc., complete.	Sqr.	4·98
15	White washing 2 coats	,,	37·66
16	Coping with burnt brick in mortar and chunnam plastering ...	R.ft.	46
17	Junglewood wrought and put up Matti or Nandi including wood oiling.	C.ft.	88·43
18	Roofing with 1st Class Mangalore tiles on teak reepers, etc., complete and fixing the eave tiles with wires.	Sqr.	11·87
19	Mangalore ridge tiles set in mortar and cement pointing, etc., complete.	R.ft.	99
20	Supplying and fixing junglewood eave boards	,,	126
21	Silicate or chocolate painting 2 coats for doors and windows ...	Sqr.	5·79
22	Providing and fixing Matti or Nandi wood double pillars with combined base and capitals for front verandah.	No.	2
23	Providing and fixing Matti or Nandi wood single pillars for rear verandah.	,,	2

No.	Items of work	Per	Quantity
24	Preparing and fixing Matti or Nandi wood railings with uprights in front verandah, complete.	Rft.	18
25	Supply and fixing stone mortor and pestle	No.	2
26	Providing and fixing Honne wood wall shelf planks 1" thick ...	S.ft.	58
27	Do jungle wood planks 1½" thick for the ceiling ...	,,	59
28	Do wall pegs	L.S.	...
29	Do seats in latrine with stone in mortar and cement plastering, complete.	,,	...
30	Constructing drains with jelly concrete foundation and brick in mortar sides and cement plastering, etc., complete.	R.ft.	69
31	Providing curb stone inside the latrine by the side of drain as shown in plan.	,,	5
32	Providing sinks in kitchen and bath room	L. S.	...
33	Do Mangalore glass roofing tiles	No.	4
34	Do and fixing 6" dia. zinc sheet chimny with cap on roof for the escape of smoke.	,,	2
35	Ornamental works such as pilasters in front at corners and patties and cornice mouldings over windows in front.	L. S.	...
36	Providing chunnam borders or binding walls over roof ...	R.ft.	37
37	Supplying and fixing 2" dia. galvanised iron pipes of 2 feet long in drains of bath and kitchen.	No.	2
38	Sundry works such as constructing a platform for keeping water vessels, etc., and a brick in clay chimny in bath room and other works found necessary during execution.	L. S.	...

Notice dated 27th October 1930.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Shimoga Division, up to 26th November 1930, till 3 P.M., for constructing Sub-Assistant Shrgeon's Quarters at Anavatti in Sorab Taluk. An approximate estimate of qantities is given below. These quantities are not guaranteed. The work should be compteted by the end of June 1931.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees two hundred only in cash or Governmentt Promissory Notes, as earnest money, and be superscribed "Tender for constructing Sub-Assistant Surgeon's Quarters at Anavatti in Sorab Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any rebly.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate of quantities for constructing quarters for the Sub-Assistant Surgeon at Anavatti, Sorab Taluk:—

No.	Items of work	Per	Quantity
1	Earthwork excavation and filling in basement	C.yd.	68
2	Stone jelly concrete in chunnam mortar	C.ft.	594
3	Filling in foundation with stone in clay including basement ...	,,	2,081
4	Burnt brick in mortar (superstructure)	,,	1,479
5	Burnt stone slabs 4½" to 6" thick neatly dressed and fixed ..	S.ft.	296
6	Plastering with chunnam mortar	Sqr.	40·09
7	Pointing to basement with cement mortar	,,	5·22
8	Masonry pillars in burnt brick in mortar, including plastering and cornice, etc., complete (9" x 9" x 6' x 10").	No.	4
9	Whitewashing 2 coats	Sqr.	40·99

No.	Items of work	Per	Quantity
10	Flooring with 3" jelly concrete in mortar and cement plastering including cutting tiles, etc.	Sqr.	6·54
11	Coping with burnt brick in mortar including plastering, complete	R.ft.	54
12	Teakwood doors with battened shutters, etc., complete ..	S.ft.	225
13	Teakwood windows with battened shutters with iron bars, etc., complete.	,,	48
14	Teakwood ventilators with glazed shutters with iron bars, etc., complete.	,,	36
15	Silicate painting	Sqr.	5·80
16	Jungle wood wrought and put up including wood oiling ..	C.ft.	89·65
17	Roofing with 1st Class Mangalore tiles on teak reepers, etc., complete.	Sqr.	14·98
18	Mangalore ridge tiles set in mortar	R.ft.	155
19	Teakwood eave boards including painting.	,,	235
20	Providing valleys at the commencement of office room with zinc sheets over ⅜" teak planks.	L. S.	..
21	Tarring wall plates and sides of doors, etc.	,,	...
22	Providing stone mortar and pestle	,,	...
23	Do sinks in bath and kitchen	,,	..
24	Constructing seats in latrine, etc.	,,	...
25	Providing 6" dia. chimneys for the escape of smoke in bath and kitchen.	No.	2
26	Providing 2" dia. galvanised iron pipes 2' long and providing hearths, etc.	L. S.	...
27	Providing Mangalore glass tiles ... ,, ...	No.	4
28	Constructing drain with jelly concrete foundation and brick in mortar sides and cement plastering, complete, and constructing a cistern outside to collect waste water	L. S.	...
29	Providing and fixing wall pegs with Honne wood planks 1" thick to keep things.	,,	...
30	Clearing ground, levelling sides and unforeseen works, etc. ...	,,	...

K. VENKATARAMAIYA,
Executive Engineer.

WATER SUPPLY DIVISION.

Abstract Notification dated 23rd—25th October 1930.

The attention of the public is invited to the detailed notification, calling for sealed tenders for laying 4" cast iron delivery and distribution pipes for Water Supply to the Northern Extension and Kuripalya at Tumkur published on page 1350 of Part VI of the *Mysore Gazette*, dated 30th October 1930.

The last day for the receipt of tenders is 14th November 1930.

M. NARASIMHAIYA,
Executive Engineer.

OFFICE OF THE EXECUTIVE ENGINEER, GAUGING AND UPPER CHANNELS DIVISION, MYSORE.

Notification dated 30th October 1930.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Gauging and Upper Channels Division, Mysore, up to 5 P.M., on Saturday the 22nd November 1930, for the following items of work :—

(i) Supplying and fixing of teakwood planks over C. D. S. and Devaroy anicuts.
(ii) Packing joints between planks.
(iii) Supplying and fixing needle shutters for the Scouring Sluice in the body wall of Devaroy anicut.

1. An approximate estimate of quantities required is given below with the specification. The work should be completed not later than the end of January 1931. Further information required, if any, may be obtained at the Executive Engineer's Office between the hours of 11 A.M. and 5 P.M. on working days.

2. The tenders should be submitted on printed forms which may be obtained from the Executive Engineer.